

To: 1 120679 2-13
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
206 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-21,034-0000 96R
SE NE NW, SEC. 20, T. 23 S, R. 15 W/E
4290 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9354
Operator: Central Energy Corporation
Name
Address P.O. Box 47590
Wichita, KS 67201

Lease Name Cossman Well # 6
County Pawnee 133.70
Well Total Depth 4114 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 387

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 13 Month: 2 Year: 19 92

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers (phone) 316-793-9711

was: 5 1/2" at 4109' w/125 sx cement, PBTD 4109', Perfs at 4072-77, 4079-82'
1st plug sand back to 4020' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 13 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4020' and dumped 5 sx cement
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Pumping pressure 550 psi and shut in 200 psi.

RECEIVED
STATE CORPORATION COMMISSION

FEB 18 1992

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1971 CONSERVATION DIVISION
(If additional description is necessary, use BACK of this report.)

INVOICED

observe this plugging.

DATE 2-21-92

Signed [Signature]
(TECHNICIAN)

INV. NO. 34615