

To: 120747
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-29 PI NUMBER 15-145-20,941-0000 207R

NE SE NW, SEC. 20, T. 23 S, R 15 W/E
3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9354
Operator: Central Energy Corporation
Name & Address P.O. Box 47590
Wichita, KS 67202

Lease Name Cossman Well # 5
County Pawnee
Well Total Depth 4135 134.39 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 358

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 4 p.m. Day: 29 Month: 10 Year: 1992

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

Work: 5 1/2" at 4130' w/125 sx cement, 5 1/2" squeezed at 1140' w/300 sx cement, 700' of stretch
PBTD 3820', Perfs at 3786-91'

1st plug sand back to 3700' and dump 4 sx cement on top of sand through bailer,
2nd plug pull pipe and pump 3 sx hulls and 200 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 29 Month: 10 Year: 1992

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3730' and dumped 5 sx cement on
top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls and 200 sx cement.
Pumping pressure 0-150 psi and shut in 75 psi.

RECEIVED
STATE CORPORATION COMMISSION

NOV 2 1992

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 720' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(Buyer/contractor) observe this plugging.

DATE 11-4-92

INV. NO. 36672

Signed Dean Parkin
(TECHNICIAN)