

To: 1 041145  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 145-20,475 -0000  
NW SE NW, SEC. 20, T 23 S, R 15 W/2  
3660 feet from S section line  
3660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 3959  
Operator: Siroky Oil Management  
Name & Address P.O. Box 464  
Pratt, KS 67124

Lease Name Crossman Well / 2  
County Pawnee  
Well Total Depth 4139 134.52 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 352

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 10:30 a.m. Day: 9 Month: 2 Year: 1996

Plugging proposal received from Kent Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

work: 5 1/2" at 4139' w/125 sx cement, PBD 4115', Perfs at 4090-4100'

1st plug sand back to 4040' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Bill Johnson (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:15 a.m. Day: 9 Month: 2 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 4040' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 800 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2129' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED (Date cancelled) observe this plugging.

DATE 2-29-96  
INV. NO. 44910

2002  
2-9-96

Signed Stephen J. Pfeifer (TECHNICIAN)