

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-159 21,096-0000 ✓

245 North Water
Wichita, KS 67202

Operator's Full Name Dakota Resources, Inc.

Complete Address 2900 Security Life Bldg, Denver, Colorado

Lease Name O'Neill Well No. 26-2

Location C SE NW SW Sec. 2 Twp. 21 Rge. 10 (East) (West)

County Rice Total Depth 3430'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Allen Drilling Co. and Halliburton Company

Address Box 1389, Great Bend, Kansas License No. _____

Operation Completed: Hour: 10:30 AM Day: 27 Month: January Year: 1981

The above well was plugged as follows: 8 5/8" - 274' Cem. Circ.

Hole Filled with mud. 50 sacks 50-50 Pozmix w/4% gel and
3% cal. chloride pumped through drill pipe at 300'. Hole
Filled with mud to 40'. Plug and 1/2 sack hulls pushed to
40' and hole cemented to base of cellar with 10 sacks
Cement. Rathole cemented with 5 sacks Cement.

STATE CORPORATION COMMISSION
JAN 30 1981
CONSERVATION DIVISION
WICHITA, KANSAS

I hereby certify that the above well was plugged as herein stated

DATE 2-23-81

Signed: [Signature]
Conservation Division Agent

INV. NO. 4637-W