

Yp
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-145-30178-0001

RECEIVED
STATE CORPORATION COMMISSION

SEP 12 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Max Cohen

Complete Address: Box 13528 Phoenix, Arizona

Lease Name Grizzell Well No. 1

Location NE NE SE Sec. 4 Twp. 23 Rge. (E) (W) 15

County Pawnee Total Depth 4067

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glenn & Smith

Address: Ellinwood, Kans License No. 396

Operation Completed: Hour 11AM Day 10 Month 9 Year 63

The Above well was plugged as follows:

8 5/8" 250' circulated with cement - 5 1/2" 4065' with 100 sax cement - PB to 4034' - perforated 4012'

Filled with sand to 4000', set 5 sax cement with dump bailer - pulled 3354' 5 1/2" - filled hole with heavy chunk mud to 250', set 30 sax cement at 250' - heavy chunk mud to 35', set bridge and 10 sax cement to bottom cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 9/12/63
INV. NO. 9431-W

Signed: *Edon Petty*
Well Plugging Supervisor

INVOICED