

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-145 - 26945-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Abercrombie Drilg. Co. Inc.

Complete Address 801 Union Center Wichita 67202

Lease Name ZOOK Well No. 1

Location NW-NE-NE Sec. 6 Twp. 23 Rge. 15 (East)(West)

County Pawnee Total Depth 4050

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie & Sun Cementing

Address _____ License No. _____

Operation Completed: Hour: 11:30 AM Day: 18 Month: 5 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" S.P. to 364' w/ 275 SX common 2% gel - 3% cc
4 1/2" @ 4048' w/ 50 SX Pozmix & 250 SX common
Perf: 900-901 w/ 450 SX common (Cement to 500')
Perf: 480-81 w/ 150 SX Light (Cement to surface)
Perf 3968-72 - cast iron bridge plug @ 3925'
Perf: 3881-88 - 3786-90 - 3755-60 Fluid level @ 1000'
No 4 1/2" pipe removed from hole - Plug: →
70 cement → 10 gel → 1 hull → 10 gel - plug →
(w/ 3 SX hulls mixed in) 90 cement
 Amount of Surface Casing: 364' not plus 500' & Shut in 300'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Steve Dumont
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I was at KCC meeting in Wichita

RECEIVED
STATE CORPORATION COMMISSION
JUN - 2 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: Steve Dumont
Conservation Division Agent
INVOICED
DATE 6-1-82
INV. NO. 308-A