

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

AMENDED

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

API NUMBER n/a

LEASE NAME Grant

WELL NUMBER 4

1750 Ft. from S Section Line

1050 Ft. from E Section Line

SEC. 4 TWP. 20S RGE. 11 (N) or (W)

COUNTY Barton

Date Well Completed 1/28/65

Plugging Commenced 11/9/94

Plugging Completed 11/10/94

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE#(918) 491-4314 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? on old form If not, Is well log attached? -

Producing Formation Lansing Depth to Top 3087 Bottom 3312 T.D. 3333

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Lansing</u>	<u>Oil</u>	<u>3087</u>	<u>3312</u>	<u>8 5/8</u>	<u>241</u>	<u>-0-</u>
				<u>4 1/2</u>	<u>3332</u>	<u>1928</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. CIBP @ 3035' w/1 sx cmt. Shot 4 1/2" casing @ 2500', 2300', & 1928'. POOH & LD. Pumped 65 sxs cmt w/300# hulls @ 1350'. Pumped 35 sxs cmt w/100# hulls to 575'. Circulated to surface from 275' with 100 sxs cmt + 100# hulls.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P. O. Box 209, Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 10th day of January, 1995

MELISSA A MCWHIRT
Notary Public - Oklahoma
TULSA COUNTY
My Commission Expires
March 21, 1998

Expires: March 21, 1998

Form 02-
Revised 05-8

DRILLER'S LOG

COMPANY: Herman George Kaiser, Oil Producer
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: GRANT A-#4
 LOCATION: SE NW SW Sec. 4-20N-11W
 Barton County, Kansas
 COMMENCED: 1-21-65
 COMPLETED: 1-28-65

0	70	Sand & Gravel
70	218	Shale
218	241	Redbed
241	510	Redbed & Shale
510	558	Anhydrite
558	1350	Redbed & Shale
1350	3255	Lime & Shale
3255	3333	Lime
	<u>3333</u>	<u>Rotary Total Depth - D. & A.</u>

Set 3 5/8" used surface casing @ 241' cemented with 225 sacks Common Sunset with 2% Gel

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Grant A-#4 well located SE NW SW of Section 4, Township 20 South, Range 11 West, Barton County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) ss
 COUNTY OF BARTON)

Sworn and subscribed to and before me, a Notary Public, in and for Barton County, Kansas, this 1st day of February, 1965.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:
April 1, 1967

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 21 1994
 WICHITA, KANSAS