

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Barton County, Sec. 27 Twp. 19S Rge. 15 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NW SE

Lease Owner Schermerhorn Oil Corporation

Lease Name Zimmer Well No. /

Office Address 714 First Nat'l Bldg., Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-14 19.53

Application for plugging filed 10-14 19.53

Application for plugging approved 10-14 19.53

Plugging commenced 10-14 19.53

Plugging completed 10-20-53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production -- 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 3611 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	885	8 5/8	Cemented	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ----- feet to ----- feet for each plug set.

3611 - 885 Mud  
885 - 880 Cement Plug  
880 - Bottom of Cellar - Cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Badger Drillers, Inc.

Address Great Bend, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

F. M. Hamner (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. M. Hamner

714 First Nat'l Bldg., Tulsa, Oklahoma


(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of November, 19.53.

Opal Gulick  
Notary Public.

My commission expires 10-20-57

23-8390-s 6-51-20M



11-4-53

BADGER DRILLERS, INC.  
714 FIRST NATIONAL BUILDING  
TULSA, OKLAHOMA

15,009.00 311.00.00

ZIMMER NO. 1  
NW/4 NW/4 SE/4 Sec. 27, T-19S, R-15W  
Barton County, Kansas

Schermerhorn Oil Corporation

8 5/8" O.D. Casing Cemented at 885'  
Drilling Started 10-4-53  
Drilling Completed 10-17-53

<u>From</u>	<u>To</u>	<u>Formation</u>	<u>Remarks</u>
0	250	Clay & shale	
250	325	Shale	
325	450	Sand Shale	
450	877	Red Bed & Shale	
877	885	Anhydrite	8 5/8" O.D. Casing set @ 885' with 450 sacks cement
885	915	Anhydrite	
915	1215	Shale & Shells	
1215	1370	Red Bed	
1370	1690	Shale & Shells	
1690	1835	Lime & Shale	
1835	2220	Lime	
2220	2890	Lime & Shale	
2890	3611 1/2	Lime	Total depth - Dry Hole

This is a certified true copy of the Driller's Log as shown on the daily drilling reports.

BADGER DRILLERS, INC.

By Henry J. Herma

Subscribed and sworn to before me this

20th day of October, 1953.

Opal Gabriel  
Notary Public

My Commission expires 10-20-57

PLUGGING  
T-19S R-15W  
SEC 27  
PAGE 37 LINE 13

RECEIVED  
OCT 21 1953  
CONSERVATION DIVISION  
Wichita, Kansas

COPY