


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Barton County, Sec. 15 Twp. 19 Rge. (E) 15 (W)
Location as "NE/CNW/SW" or footage from lines NE SE SW
Lease Owner Home-Stake Production Company
Lease Name Breeden Well No. 1
Office Address 1015 Philtower, Tulsa, Oklahoma 74103
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed November 20 1968
Application for plugging filed April 10 1969
Application for plugging approved _____ 19____
Plugging commenced April 28 1969
Plugging completed May 13 1969
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3574 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	920'	8 5/8"	920'	none
		0	3569'	5 1/2"	3569'	2926.83

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back hole from 3585' to 3250' and dumped 5 sacks of cement.
Pushed plug to 370'. Mixed and dumped 6 sacks of cement plus 15 gal. of sand on plug (from 370' to 350'). Dumped 5 yards of ready mix plugging cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pipe Pullers, Inc.
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Evelyn Roth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of May 1969
George A Meyer Notary Public.

My commission expires Feb. 10, 1971

KANSAS GEOLOGICAL SOCIETY
508 East Murdoch
Wichita, Kansas
MAR 1 1969

Distributed by
KANSAS GEOLOGICAL SOCIETY
508 East Murdoch
WICHITA, KANSAS 67214

5009.20303.00.00

COPY

ME 515 3M
Section 15-198-15M
Barren County, Kansas

Well Owner: Hesperago Production Company
Farm Name: Freedom #1
Date Started: November 8, 1968
Date Completed: November 20, 1968
Total Depth: 3574'
Casing: 8-5/8" set at 920' Cemented
5 1/2" set at 3569' Cemented
Operator: Peet Brothers, Inc.

Bottoms of the formations are as follows:

Surface Clay	0 - 288
Sand	105
Red bed	605
Anhydrite	905
Shale	1968
Lime and Shale	2875
Lime	3525
Lime and Chert	3570
Chert	3574
Total Depth	3574

This is to certify that the above information is true and correct to the best of our knowledge.

PEET BROTHERS, INC.

Donald O. Peet
President

AND SWORN to before me this 26th day of November, 1968.



Donald S. Williamson
DONALD S. WILLIAMSON
Notary Public

My Commission Expires 6-27-70