

15.009.06239.00.00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Barton

County. Sec. 35 Twp. 19 Rge. (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines. SE 1/4 NE 19

Lease Owner WHITE EAGLE OIL COMPANY

Lease Name RUSSELL "B" Well No. B-2

Office Address First National Building Tulsa 3, Oklahoma.

Character of Well (completed as Oil, Gas or Dry Hole) DRY

Date well completed 10-13-53 19

Application for plugging filed 10-13-53 19

Application for plugging approved 10-26-53 19


Plugging commenced 10-13-53 19

Plugging completed 10-28-53 19

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3539 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Tops from Electric Log K.B. Measurements 1876' CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner shale		3091		8-5/8"	805	none
Toronto		3105		5-1/2"	3414	2909'
Douglas		3122				
Iatan (Brown Lime)		3184				
Lansing		3195				
Conglomerate		3432				
Arbuckle		3534				
Total depth (Electric Log)		3540				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

LANE WELLS PLUG @ 3371
 " " 3349
 " " " 3230
 Heavy mud from bottom to 300'
 Rock Bridge 300 to 290'
 20 sacks cement 290 to 230'
 Heavy mud 230 to 35'
 Rock bridge 35 to 30'
 10 sacks cement 30 to surface cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pulling Inc. Permit #21
 Address 629 West Broadway Stafford, Kansas.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

M.J. Heald Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M.J. Heald Jr. Chief Engineer
First National Building Tulsa 3, Oklahoma. (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November 19 53

My commission expires 8-29-55

Notary Public.

24-7368-5 3-53-20M

PLUGGING
 FILE SEC 35 T 19 R 14W
 BOOK PAGE 138 LINE 9

NOV 17 1953
 CONSERVATION DIVISION
 Wichita, Kansas

11-17-53

DRILLERS LOG

Company: Helmerich & Payne

SE NW NE
Sec. 35 Twn. 19S Rge. 14W

Farm: Russell B Well No. 2
Total Depth: 3539'

County: Barton,
Kansas

Comm: 9-16-53 Comp: 9-27-53
Contractor: Peel Brothers, Inc.

Elevation:

Casing:

8 5/8" @ 805' Cem.
5 1/2" @ 34' Cem.

Production:

Figures below indicate bottom of formation

Sand and Shale	0'	300'
Sand		410
Red Bed		798
Anhydrite		805
Shale		1200
Shale lime		1900
Shale		2210
Shale lime		2630
Lime		2730
Arbuckle		3539
Total Depth		3539

This is to certify that the above information is to the best of my knowledge true and correct.

PEEL BROTHERS, INC.

BY *A. C. Sutton*

SUBSCRIBED AND SWORN to before me this 6th day of October 1953
My Commission expires Jan. 11, 1955

Liquid K. Lewis
Notary Public

PLUGGING
FILE SEC 35 T 19 R 14W
BOOK PAGE 138 LINE 9

STATE CORPORATION C.
NOV 11
COMMUNICATION DIVISION
Wichita, Kansas