


15.009.00060.00.00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Building Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Flat

Barton County. Sec. 14 Twp. 19 Rge. 14 (E) W (W)
Location as "NE/CNW1/4SW1/4" or footage from lines SW SW SE
Lease Owner Duke & Wood Drilling Company, Inc.
Lease Name Brewer Well No. 1
Office Address Box 194, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 27, 19 52
Application for plugging filed March 27, 19 52
Application for plugging approved March 27, 19 52
Plugging commenced March 27, 19 52
Plugging completed March 27, 19 52
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3507 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: 8 5/8", 812', None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 270 ft., set bottom plug, dumped 20 sacks cement on same. Filled with heavy mud to 35 ft., set top plug, dumped 10 sacks cement on plug and filled to bottom of cellar.

Handwritten date: 4-11-52

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Duke & Wood Drilling Company, Inc.
Address Box 194, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Cecil M. Olson (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Cecil M. Olson

Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 3rd day of April, 19 52

Handwritten signature: Dean C. Looley

Notary Public.

My commission expires April 29, 1953.

PLUGGING FILE SEC 14 T 19 R 14 W BOOK PAGE 4 LINE 29

15.009.00060.00.00

WELL LOG
Brewer #1
SW SW SE Section 14-19-14W
Barton County, Kansas

	Elevation	D. F.
Anhydrite	1875	(+1068)
Heebner	809	(-1226)
Lansing	3103	(-1327)
Conglomerate	3204	(-1552)
Arbuckle	3429	(-1622)
	3499	

0-60	Surface clay, sand and gumbo
60-175	Sand & shale
175-245	Shale and sand streaks
245-360	Shale, sand & Dakota sand
360-575	Red bed and shale
575-720	Sand, shale, shells and red rock
720-797	Shale, shells and red bed
797-809	Chalk and soft anhydrite
809-829	Anhydrite
829-1270	Shale, shells and red bed
1270-1600	Shale, salt and shells
1600-1725	Shale, shells and lime
1725-2035	Lime and shale
2035-2445	Lime and shale
2445-2785	Lime and shale
2785-2845	Lime and shale
2845-2955	Lime
2955-3070	Lime
3070-3200	Lime
3200-3280	Lime
3280-3373	Lime
3373-3429	Lime
3429-3499	Conglomerate
3499-3507	Arbuckle
3507	TOTAL ROTARY DEPTH

A F F I D A V I T

STATE OF Kansas, COUNTY OF Barton SS

I, Lynn O. Duke, of the DUKE & WOOD DRILLING COMPANY, INC. being first duly sworn on oath, state; That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Lynn O. Duke
Vice-President.

Subscribed and sworn to before me this 10th day of April 1952.

PLUGGING
FILE SEC. 14-19-14W
BOOK PAGE 4-19-29-1952
My commission expires: April 29, 1953.

Dean E. Looney
Notary Public