


STATE OF KANSAS
STATE CORPORATION COMMISSION

15.009.30838.00.00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bixing Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 14 Twp. 19S Rge. 14 (X) (W)
Location as "NE/CNW/SW" or footage from lines 200' N, 200' E CSLS, NW/4
Lease Owner Ben F. Brack Oil Company, Inc.
Lease Name Alefs "A" Well No. 1
Office Address 309 Brown Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 4-13-53 19
Application for plugging filed 4-3-53 19
Application for plugging approved 4-6-53 19
Plugging commenced 4-13-53 19
Plugging completed 4-13-53 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Conglomerate Depth to top 3463 Bottom _____ Total Depth of Well 3579 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface clay, Shale, shells, red bed,	sand, & Anhydrite	0	837	8 5/8"	837'	None
Shale, shells, salt,	& Lime	837	3579	5 1/2"	3578'	1894.56

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3275 feet to 3235 feet for each plug set.

Plugged back to 3275' with sand. Set cement plug from 3275-35 with 5 sax cement. Filled with heavy mud and cemented with 100 sax cement. Leveled location.

5-1-53


RECEIVED
STATE CORPORATION COMMISSION
MAY 1 1953

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pipe Pulling Inc.
Address 629 W. Broadway, Stafford, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Ben F. Brack (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ben F. Brack
309 Brown Building, Wichita, Kansas (Address)

Subscribed and sworn to before me this 29th day of April, 1953
Gertrude Crist
Notary Public.



PLUGGING
FILE SEC 14 T 19 R 14 W
BOOK PAGE 90 LINE 10

15.009.30838.00.00

BEN F. BRACK OIL COMPANY, INC.
309-10 BROWN BUILDING
WICHITA 2, KANSAS

ALEFS A #1 200' N, 200' E of Center of South line NW/4 Sec. 14-19S-14W
Barton County, Kansas
Total Depth: 3579'
Elevation: 1877'
 1875'
Commenced: 8-19-52
Completed: 8-30-52

WELL LOG

Surface Clay & Shale	0 -	98'
Sand		109
Shale & Shells		338
Sand - Shale		565
Shale & Red Bed		827
Anhydrite		837
Shale & Shells		1235
Shale, Shells, & Salt		1580
Lime		1640
Lime - Shale		1855
Shale		1950
Lime		2170
Shale & Lime		2315
Shale		2530
Shale & Shells		2725
Shale & Lime		2865
Lime		2950
Shale & Lime		2968
Lime		3163
Shale & Lime		3265
Lime		3483
Lime & Shale		3579 T.D.

CASING

8 5/8" 837'
5 1/2" 3578'

To the best of my knowledge,
the above is a true and correct
statement of the depths and
formations and where found.

BEN F. BRACK OIL COMPANY, INC.

By *Ben F. Brack*

WITNESSED:

Lertunde Cust

September 4, 1952

RECEIVED
CORPORATION
ADJ
CONSTRUCTION

PLUGGING
FILE SEC 14 T 19 R 14W
BOOK PAGE 90 LINE 10