

15.009.30355.00.00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form GP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Barton County, Sec. 14 Twp. 19S Rge. (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines S/2 SE SE
Lease Owner Circle Oil Company, Inc.
Lease Name Brewer Well No. 1
Office Address 500 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 13, 1966
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced March 13, 1966
Plugging completed March 13, 1966
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation Depth to top Bottom Total Depth of Well 3532 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	808	8-5/8"	3/7/66	
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 320 Feet; 1/2 sack Hulls and Plug bridged and 25 sacks cement through the drill pipe; Heavy Mud to 40 feet; 1/2 sack Hulls and Plug bridged; cement to base of cellar; 2 sacks in rat hole. Job completed at 4:00 P.M.

RECEIVED
WICHITA CONSERVATION DIVISION

MAR 24 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co., Inc.
Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Lawrence F. Gray (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence F. Gray
500 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of March 1966

Louise K. Whitted
Notary Public.

My commission expires November 26, 1966.

15. 009 .30355.00.00

DRILLERS LOG

BREWER NO. 1

CASING RECORD:	COMPANY:	Circle Oil Co.	DESCRIPTION:
8-5/8" @ 808' w/400 sax cement	CONTRACTOR:	Sage Drilling Co.	S/2 SE SE Sec. 14-19S-14W Barton County, Kansas
TOTAL DEPTH: 3532'	COMMENCED:	March 7, 1966	Elevation: 1875KB
	COMPLETED:	March 13, 1966	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Shale	0	318	
Sand & Shale	318	347	
Red Bed, Shale & Shells	347	793	
Anhydrite	793	819	
Shale	819	842	
Red Bed, Shale & Shells	842	1600	
Sandy Lime & Shale	1600	1730	
Lime & Shale	1730	2440	
Shale & Lime	2440	2830	
Lime & Shale	2830	3245	
Lime	3245	3256	
Lime & Shale	3256	3395	
Cherty Lime	3395	3487	
Lime & Shale	3487	3532	

RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1966

CONSERVATION DIVISION
Topeka, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING COMPANY, INC.

By Lawrence F. Gray
Lawrence F. Gray

Subscribed and sworn to before me this 15th day of March, 1966.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1966.