

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County.

Sec. 10 Twp. 19 Rge. 14 W (W)

Location as "NE/CNW/SW" or footage from lines NE NE SE

Lease Owner Northern Pump Co., Et Al

Lease Name Warnken Well No. 1

Office Address Box 94, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 16, 1957 19

Application for plugging filed September 16, 1957 19

Application for plugging approved September 16, 1957 19

Plugging commenced September 16, 1957 19

Plugging completed September 16, 1957 19

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3614 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
	Surface Pipe	0	850'	8-5/8"	850'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud. Set bridge at 300'. Ran 25 sacks cement through drill pipe 300' up. Set bridge at 20' below ground level. Run 5 sacks cement 20' to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Isern Drilling Company
Address Box 45, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON

I, M. M. Shropshire

(employee of owner) or SS of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. M. Shropshire

Lyons, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of September 19 57

My commission expires Feb. 10, 1959.

George A. Meyer
Notary Public.

PLUGGING
FILE SEC 10 T 19 R 14W
BOOK PAGE 46 LINE 4

FILED
COMMISSION

9-19-57

WELL LOG

NORTHERN PUMP ET AL, Owner - WARNKEN #1
NE/4 NE/4 SE/4 Section 10, Township 19S, Range 14W,
Barton County, Kansas

ELEVATION: 1883 DF

Figures indicate bottom of formation:	
0	to 335 shale & shells
	435 sand
	840 Red rock
	870 Anhydrite
	880 sand
	1325 shale & shells
	1600 salt
	2330 lime & shale
	2615 shale & shells
	3538 lime & shale
	3614 lime & chert
	3614 Rotary TD
	D & A

PIPE RECORD:

8-5/8" set at 850'
Cemented with 450 sacks cement,
700# Calcium Chloride
September 7, 1957

Rotary Commenced 9-7-57
Completed 9-16-57

STATE OF KANSAS)
COUNTY OF BARTON) SS

I, M. M. Shropshire, Drilling Superintendent of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

M. M. Shropshire

Subscribed and Sworn to before me this 17th day of September, 1957.

[Signature]
Notary Public

My commission expires Feb. 10, 1959

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1957

PLUGGING
FILE SEC. 10 T. 19 R. 14W
BOOK PAGE 46 LINE 4

CONSERVATION DIVISION
Wichita, Kansas