


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Payment  
Mail or Delivery Report to:  
Conservation Division  
State Corporation Commission  
800 Brick Building  
Wichita, Kansas

15.009.00670.00.00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barton County. Sec. 32 Twp. 19 Rge. 13 (E) (W)  
Location as "NE/CNWxSWx" or footage from lines NW SW SE  
Lease Owner Honaker-Davis Drlg. Co.  
Lease Name Wood Well No. 1  
Office Address 2008 Lakin Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-3 19 56  
Application for plugging filed 5-2 19 56  
Application for plugging approved 5-2 19 56  
Plugging commenced 5-3 3:00 A.M. 19 56  
Plugging completed 5-3 4:00 A.M. 19 56  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Brundge  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3490 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	754	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with Heavy Rotary mud to 300'. Put plug and 1/3 sack hulls at 300. Dumped 25 sacks cement on top of plug through drill pipe. Filled hole to 35' with Heavy Rotary Mud. Put in 1/3 sack hulls ahead of plug at 35'. Dumped in 10 sacks cement. Also dumped 5 sacks cement in Rat Hole.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 5 1956

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_  
Address \_\_\_\_\_

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Bill Edwards (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Edwards  
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of May, 1956

My commission expires 6-25-59  
Kenneth G. Fischer, Notary Public.

**PLUGGING**  
FILE SEC. 32, T. 19, R. 13W  
BOOK PAGE 59 LINE 10

15.009.00670.00.00

DRILLERS LOG

WOODS No. 1  
Loc: NW SW SE  
Sec: 32-19-13  
Barton County, Kansas  
Company: Honaker-Davis Drlg. Co., et al  
Contractor: Honaker-Davis Drlg. Co.

Comm: 4-23-56  
Comp: 5-3-56  
Rotary Total Depth: 3490  
Casing: 8-5/8" at 754'  
D & A

0	130	Sand & Gravel	
130	185	Blue Shale	
185	300	Shale	
300	370	Sand	
370	580	Red Bed	
580	745	Red Bed & Shale	8-5/8" casing cemented at
745	770	Anhydrite	754' with 400 sacks cement
770	930	Shale & Red Bed	& 8 sacks calcium chloride
930	1350	Shale & Shells	
1350	1530	Salt & Shale	
1530	3431	Lime & Shale	
3431	3467	Conglomerate	
3467	3475	Arbuckle	
3475	3490	Lime & Shale	
3490		Total Rotary Depth	D & A

I certify that this is the true and correct copy of the above log to the best of my knowledge.

*H. S. Forbes*  
H. S. Forbes

Subscribed and sworn to before me this 4th day of May, 1956.

*Kenneth G. Fischer*  
Kenneth G. Fischer, Notary Public

My commission expires: 6-25-59

RECORDED  
STATE CORPORATIONS

COMMISSION STATE NOTARY PUBLIC

**PLUGGING**  
FILE SEC 32 19 R 13W  
BOOK PAGE 59 LINE 10