


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 3 Twp. 19S Rge. 13W (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SW NE
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name Benjamin "A" Well No. 2
Office Address 800 Bitting Building, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed November 9, 1962 19
Application for plugging filed November 27, 1962 19
Application for plugging approved November 29, 1962 19
Plugging commenced November 29, 1962 19
Plugging completed December 6, 1962 19
Reason for abandonment of well or producing formation non-productive in commercial quantities
If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3406 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200	cemented
				5 1/2"	3392	2570'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug at 3350 feet
Filled with sand from 3350 feet to 3145 feet and ran
4 sacks of cement from 3145 feet to 3116 feet
Pumped 10 sacks of mud and 80 sacks ~~ex~~ of cement
in 8 5/8" pipe to plug well

RECEIVED
STATE CORPORATION COMMISSION

MAR 26 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn and Smith Pipe Pulling Company
Address Ellinwood, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul
800 Bitting Building, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of January, 19 63

My commission expires August 10, 1965

Virginia Mendenhall
Notary Public.



15.009.06/94.00.00

WELL LOG

Alpine Oil & Royalty Co., Inc.

Commenced: October 19, 1962

Contractor: Quaker Drilling Co., Inc.

Completed: October 26, 1962

Benjamin No. 2-A
SE SW NE Sec. 3-19S-13W
Barton County, Kansas

Elevation: 1875 K. B.

Production: D. & A.

Casing Record:

Set 8 5/8 inch casing at 200 feet with 175 sacks cement
Set 5 1/2 inch casing at 3392 feet with 100 sacks cement

RECEIVED

STATE CORPORATION COMMISSION

NOV 29 1962

(Figures Indicate the Bottom of the Formations)

CONSERVATION DIVISION
Wichita, Kansas

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil & Clay	90	Anhydrite	753 +1122
Sand	105	Heebner	3045 -1170
Shale	200	Brown Lime	3135 -1260
Sand and Shale	410	Lansing	3149 -1274
Red Bed	753	Base of Kansas City	3370 -1495
Anhydrite	780	Conglomerate	3375 -1500
Shale and Shells	1500	Arbuckle	3390 -1515
Lime and Shale	1950	Rotary Total Depth	3393 -1518
Sandy Lime & Shale	2050	Cable Tool Depth	3406 -1531
Lime and Shale Streaks	2230		
Lime and Shale	3393		

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the No. 2-A Benjamin, drilled in the SE SW NE of Section 3, Township 19 South, Range 13 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: Thomas M. McCaul
Thomas M. McCaul, President

SUBSCRIBED AND SWORN TO before me a Notary Public this 15th day of November, 1962.

Virginia Mundell
Virginia Mundell, Notary Public

My Commission Expires;
August 10, 1965