

15.009.30482.00.00

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 1 Twp. 19S Rge. (E) 13W(W)  
Location as "NE/CNW%SW%" or footage from lines W/2 SE SE  
Lease Owner Three G Oil, Inc.  
Lease Name Berchek Well No. 1  
Office Address 1101 Wichita Plaza, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 11, 1966  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced November 11, 1966  
Plugging completed November 11, 1966  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Flat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Don Truan)

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3423 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	0	298'	8-5/8"	11/3/66	-----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy Mud from Total Depth to 250 feet;  
Hull Plug and HOWCO Plug and 25 sacks  
cement thru the drill pipe; Heavy Mud  
from 250 feet to 40 feet; Hulls & Plug  
and 10 sacks cement to base of cellar;  
2 sacks cement in rat hole. Job was  
completed @ 3:45 P.M.

RECEIVED  
NOV 17 1966  
STATE CORPORATION COMMISSION

NOV 17 1966

CONSERVATION DIVISION  
Wichita, Kansas

11-17-66

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co.  
Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Lawrence F. Gray of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described well; being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence F. Gray

500 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November, 19 66

Louise F. Whitted  
Louise K. Whitted - Notary Public.

My commission expires November 26, 1966

15.009.30482.00-00

DRILLERS LOG

BERCHEK NO. 1

CASING RECORD:	COMPANY:	Three G Oil, Inc.	DESCRIPTION:
8-5/8" @ 298'	CONTRACTOR:	Sage Drilling Co.	W/2 SE SE
w/200 sax cement	COMMENCED:	November 2, 1966	Sec. 1-19S-13W
TOTAL DEPTH:	COMPLETED:	November 11, 1966	Barton Co., Kansas
3423'			

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	40	
Surface Soil & Sandy Shale	40	300	
Shale, Shells & Red Bed	300	880	
Red Bed & Shale	880	935	
Shale & Shells	935	1555	
Shale, Shells & Lime	1555	1757	
Shale & Lime	1757	2620	
Lime & Shale	2620	2938	
Lime	2938	3045	
Shale	3045	3135	
Lime & Shale	3135	3140	
Lime	3140	3195	
Lime & Shale	3195	3270	
Lime	3270	3288	
Lime & Shale	3288	3310	
Lime	3310	3423	

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 17 1966  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Lawrence F. Gray  
Lawrence F. Gray

Subscribed and sworn to before me this 15th day of November, 1966.

Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1966.