


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

15.009.06248.00.00  
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County. Sec. 17 Twp. 19S Rge. 12 (E) W. (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW NE  
Lease Owner Alpine Oil & Royalty Co., Inc. et al  
Lease Name Sid Rusco Well No. 1  
Office Address 300 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 9th 1950  
Application for plugging filed September 9th 1950  
Application for plugging approved September 9th 1950  
Plugging commenced September 9th 1950  
Plugging completed September 9th 1950  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
Producing formation Arbuckle Depth to top 3438 Bottom 3471 Total Depth of Well 3471 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	236'	Cemented.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged heavy mud from 3471 to 236'.  
Solid plug and 15 sacks cement, mud to 35', another plug and ten (10) sacks cement.

SEP 14 1950 9-14-50

(If additional description is necessary, use BACK of this sheet)


Correspondence regarding this well should be addressed to  
Address Alpine Oil & Royalty Co., Inc.  
300 Bitting Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) Thomas M. McCaul  
President  
300 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of September, 1950.

Lawrence Allen  
Notary Public.

My commission expires August 8, 1953.



15.009.06248.00.00

WELL LOG

Alpine Oil & Royalty Co., Inc.

Elevation: 1871 R.B.

Contractor: Quaker Drilling Co., Inc.

Commenced: 9-1-50

Completed: 9-10-50

Sid Rusco No. 1

NW NW NE Sec. 17-19S-12W

Barton County, Kansas

Production: D & A

Casing Record:

Set 236' of 8 5/8" with 125 sacks cement

(Figures Indicate Bottom of Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Clay & Sandy Shale	145	Heebner	3048 -1177
Sand	168	Brown Lime	3156 -1285
Shale & Pyrites of Iron	231	Lansing	3174 -1303
Hard, white sand	275	Conglomerate	3427 -1556
Shale and Sand	400	Arbuckle	3438 -1567
Shale and Red Bed	730	Total Depth	3471 -1600
Anhydrite	765		
Shale and Shells	1510		
Lime and Shale	2785		
Lime	2925		
Lime and Shale	3396		
Lime	3427		
Conglomerate	3438		
Dolomite	3471 TD		

RECEIVED

SEP 14 1950

STATION  
KANSAS

I hereby certify that the above is a true and correct copy of Driller's Log of well drilled in the NW NW NE of Section 17, Township 19 South, Range 12 West, Barton County, Kansas.

ALPINE OIL & ROYALTY CO., INC.

By: Charles M. McCall  
President

Subscribed and sworn to before me this 11th day of September, 1950.

My commission expires:  
August 8, 1953.

Lawrence Allen  
Notary Public

PLUGGING  
FILE SEC 17-19S-12W  
BOOK PAGE 27-LINE 29