


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Road
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 23 Twp. 19 Rge. 11 (E) (W)
Location as "NE/CNWxSWx" or footage from lines SE NE NE
Lease Owner Petroleum, Inc.
Lease Name ZIEGENBUSH Well No. 1
Office Address 305 East Third, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 17, 1953
Application for plugging filed December 17, 1953
Application for plugging approved December 17, 1953
Plugging commenced December 17, 1953
Plugging completed December 17, 1953
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Greider
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3370 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	224'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up to 215' and set wooden plug. Placed
1/4 sack hulls on top of plug at 215'. Cemented
and displaced 20 sacks cement through drill pipe
onto plug and hulls at 215'. Mudded up to 35'
and set second wooden plug at 35'. Filled hole
to bottom of well cellar with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. W. Fisher (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Fisher
305 East 3rd Street, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of December, 1953

Shirley Menden
Notary Public.

My commission expires October 13, 1954.

PLUGGING
FILE SEC 23 T 19 R 11 W
BOOK PAGE 2 LINE 4

1-6-54

15.009.30912.00.00

DRILLER'S LOG ZIEGENBUSH #1

Petroleum, Inc., Operator

Section 23, Twp. 19S, Rge. 11W

Garvey Drilling Company, Contractor

Location: SE NE NE

Drilling Commenced: December 6, 1953.

County: Barton County, Kansas.

Drilling Completed: December 17, 1953.

Production: D & A

Casing Record: 8 5/8" @ 224' w/150 sax.

Figures below indicate bottom of formation:

195	Surface & Sand
224	Shale & Shells
515	Shale, Red Bed & Shells
540	Anhydrite
1385	Shale & Shells
2765	Lime & Shale
3370	Lime
3370	R.T.D.

Tops:

Heebner:	2903 (-1122)
Brown Lime:	3024 (-1243)
Lansing:	3044 (-1263)
Arbuckle:	3330 (-1549)

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W. W. Fick

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 26th day of December, 1953.

Charlotta Heisman
 Notary Public

My commission expires: October 13, 1954.

PLUGGING
 FILE SEC 23 T 19 R 11W
 BOOK PAGE 2 LINE 4