


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15.009.14/99.00.00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 18 Twp. 19 Rge. (E) 11 (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SW SW NE
Lease Owner E. H. Adair
Lease Name Robt "B"
Office Address 407 W-K-H Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 14, 19 52
Application for plugging filed April 14, 19 52
Application for plugging approved April 14, 19 52
Plugging commenced April 15, 19 52
Plugging completed April 15, 19 52
Reason for abandonment of well or producing formation Barren

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Great Bend, Ks.
Producing formation Depth to top Bottom Total Depth of Well 3421 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
	Copy of well log attached					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Placed plug at 240' put 20 sx cement on plug through drill pipe filled hole with mud up to 30' of surface, placed plug and filled hole up to surface with 10 sx cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E. H. Adair Oil Company
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Russell I. Baker (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Russell I. Baker

Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of April 19 52

RECEIVED
STATE CORPORATION COMMISSION

Notary Public.

My commission expires September 15, 1953

6-51-20M APR 25 1952

PLUGGING
FILE SEC 18 T 19 R 11 W
BOOK PAGE 9 LINE 23

CONSERVATION DIVISION
Wichita, Kansas

E. H. ADAIR OIL COMPANY

5.009.14,99.00.00

Sec. 18 T. 19 S. R. 11 W.

Robl "3" #1

SW SW NE

Conn. 4/4/52 Comp. 4/14/52

Barbon County, Kansas

258' 8 5/8" s/csg, 150 sx cement

Elevation

Est. 1796DF
1794Gr

Shale	0-30
Sand	30-50
Shale	50-258
Shale & Sand	258-605
Anhydrite	605-635
Shale	635-1380
Shale & Shells	1380-1430
Lime	1430-1482
Lime & Shale	1482-1715
Lime	1715-1830
Lime & Shale	1830-1858
Shale & Shells	1858-1964
Shale	1964-2274
Shale & Shells	2274-2605
Shale & Lime	2605-2740
Lime	2740-2957
Shale	2957-3050
Lime	3050-3347
Conglomerate	3347-3386
Lime	3386-3421

Rotary

Certified Correct

Russell Baker

RECEIVED
STATE COMMISSION
APR 25 1952
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 18 T 19 R 11 W
BOOK PAGE 9 LINE 13

15.009.14/99.00.01

Operator W & T E. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. #1 Lease Name ROSL "OWNO"

S 18 T 19 R 11 E SW-SW-NE

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
ANTH.	602	+1194		
Top.	2642	-896		
HEEB	2954	-1158		
BR. LI.	3071	-1275		
LKC	3089	-1293		
CONG. SH.	3352	-1556		
CONG. CH.	3357	-1561		
RE ARB.	3379	-1583		
ARB.	3383	-1587		
T.D.	3418	-1622		

RECEIVED
STATE CORPORATION INFORMATION
DEC 25 1981

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Signature
	Title
	Date

CONSERVATION DIVISION
Michigan Kansas