


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Barton County, Sec. 16 Twp. 19S Rge. 11 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NW  
Lease Owner C. E. Ash & L. B. Smith  
Lease Name J. C. Bieberle "A" Well No. 1  
Office Address 309 Petroleum Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 4, 19 51  
Application for plugging filed August 6, 19 51  
Application for plugging approved August 9, 19 51  
Plugging commenced August 19, 19 51  
Plugging completed August 24, 19 51  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19...  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stought, Great Bend, Kansas  
Producing formation Arbuckle Depth to top 3342' Bottom 3393' Total Depth of Well 3393 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Water	3342'	3393'	8-5/8"	241	None
				5-1/2"	3289'	2787'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to... feet for each plug set.

Sand Bridge 3130' to 3085'  
5 Sacks Cement 3085' to 3050'  
Mudded from 3050' to 200'  
Wood Plug at 200' Pumped in 60 Sacks cement by Sun Oil Well Cementing Co.  
Filled to Surface with dirt.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 6 X 1951  
CONSERVATION DIVISION  
Wichita, Kansas

9-6-51

Name of Plugging Contractor R & S Pipe Pulling Company  
Address Ellinwood, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.  
C. E. Ash (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. Ash

309 Petroleum Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 5th day of September, 1951

Charles J. Roberts Notary Public.

My commission expires October 31, 1951

23-8390-s 6-51-20M  
PLUGGING  
FILE SEC. 16 T. 19 R. 11 W. 4  
BOOK PAGE 101 LINE 26

15.009.00583.00.00

ASH & SMITH  
Bieberle A #1  
SE SE NW Sec. 16-19-11  
Barton County, Kansas.

Comm. Rig up: 5-26-51  
Comm. Drlg. : 5-28-51  
Comp. R.D. : 6-9-51  
Completed : 8-4-51  
Total Depth : 3393'

Elevation : 1785'  
Initial Prod.: Dry  
Contractor : C. E. Ash  
Tools : Rotary

CASING RECORD

Run	Pulled	Left in
241' 8-5/8 Surface Casing cemented with 125 Sacks Monarch Cement		241' 8-5/8 Surface Casing
3289' 5-1/2" 15# Casing cemented with 100 Sacks Monarch Cement		3289' 5-1/2 Casing

STRATA	DEPTH	FORMATION TOPS	DERRICK FLOOR
Clay	25		
Sand & Shale	175	Topeka	2667 (-882)
Shale	320	Heebner	2929 (-1144)
Red Bed	567	Dodge	2949 (-1164)
Anhydrite	660	Brown Line	3047 (-1262)
Shale & Sand	965	Lansing	3065 (-1280)
Shale	1060	Conglomerate	3334 (-1549)
Salt	1090	Arbuckle	3342 (-1557)
Shale & Shells	1305		
Sand & Shale	1755	Show oil 3153-3159	
Lime	1815	D.S.T. 3149-3161 Open 45 Min.	
Sand & Lime	2130	Recovered 55' slightly oil cut mud	
Lime & Shale	2775	650# B.H.P.	
Lime	2822		
Lime & Shale	3243	Show oil 3232-3242	
Lime	3255	D.S.T. 3229-3243 Open 25 Min.	
Lime & Shale	3393	Recovered 20' slightly oil cut mud	
TOTAL DEPTH	3393	350# B.H.P.	

Plugged back to 3258.  
Perforated 24 Jet Shots 3232'-3240', acidized 500 Gal. Showed little oil, Reacidized 2000 Gal. No increase in oil.

Plugged back to 3190'  
Perforated 24 Jet Shots 3153-3159, Acidized 500 Gal. Acid communicated with water zone. Squeezed 3153-3159 with 50 sacks cement. Reperforated 24 Jet Shots 3153'-3159'. Acidized 500 Gal. Squeeze job failed. Squeezed with 15 sacks cement with no results. Squeezed with 12 sacks cement, re-perforated 24 shots 3154-3158. Acidized 500 Gal. No results.

Plugged back to 3130  
Perforated 24 shots 3093-3097  
Acidized 500 Gal. No results

D & A

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

C. E. Ash  
C. E. Ash

STATE OF KANSAS, COUNTY OF SEDGWICK

Subscribed and sworn to before me this 7th day of August, 1951.

Charles H. [Signature]  
Notary Public

My commission expires October 31, 1951.

RECEIVED  
STATION  
SEP 1 1951  
GCH

PLUGGING  
FILE SEC-16-19-11  
BOOK PAGE 101 LINE 26