


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Blitt Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

NORTH



Locate well correctly on above  
Section Plat

Barton County. Sec. 26. Twp. 18. Rge. 15. (W)  
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NW - SW - SE  
Lease Owner. Riggs Supply Company  
Lease Name. Bahr "B" Well No. 3  
Office Address. 702 Union Nat'l Bank Bldg Wichita 2, Kans  
Character of Well (completed as Oil, Gas or Dry Hole). Dry Hole  
Date well completed. 1-4 1948  
Application for plugging filed. 1-15 1948  
Application for plugging approved. 1-15 1948  
Plugging commenced. February 5 1948  
Plugging completed. February 13 1948  
Reason for abandonment of well or producing formation. Dry Hole

If a producing well is abandoned, date of last production. No. 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well. C. Stough  
Producing formation. Depth to top. Bottom. Total Depth of Well. 3486 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5 "		2927' 4"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded to 3220'. Run 5 sacks cement.  
Run plug to 2800'. Mudded to 800' of top.  
Run 15 sacks cement. 15' bridge. Mudded to  
205' of top. Run 10 sacks cement.  
Well completed

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Riggs Supply Company  
Address. 702 Union National Bank Building, Wichita, Kansas.


STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, ss.  
\_\_\_\_\_, (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God.

(Signature) *E. H. Riggs*

(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of February, 1948

commission expires Nov 3, 1948



2-24-48

Notary Public.

DRILLER'S LOG

Company: E. H. Riggs

Sec. 26 Twp. 18S Rge. 15W  
50' East of NE SW SE  
(Skid Rig)  
County: Barton  
Kansas

Farm: Bahr "B" Well No. 1

Total Depth: 3486'

Comm.: 12-15-47; Comp.: 1-4-48

Contractor: Glenn Peel Drilling Co., Inc.

Elevation:

Casing:

876' 8 5/8" Cem.

3448' 5 1/2" Cem.

0 - 3450 - Rotary

3450 - 3486 - Cable Tools

Production: Abandoned

Figures below indicate bottom of formations

Surface clay & sand	0 - 170
Shale and shells	325
Shale	335
Sand	370
Shale	428
Sand	470
Sand and shale	520
Shale	540
Sand and shale	570
Shale	864
Anhydrite	890
Shale and shells	1312
Salt	1580
Lime and shale	1695
Broken lime and shale	1750
Lime	1885
Shale w/lime streaks	1855
Lime and shale	2190
Lime streaks and shale	2245
Lime	2278
Shale w/lime streaks	2640
Broken lime and shale	2870
Lime	3015
Broken lime	3099
Lime	3447
Reagan Sand	3450
T. D. for Rotary	3450

Cable Tools:

Gas Sand 3475

Gas Sand (very hard) 3481

Sand (Water) 3486

Total Depth for C. T. 3486

Plugged back and perforated. Well abandoned.

This is to certify that the above information, to the best of our knowledge, is true and correct.

GLENN PEEL DRILLING CO., INC.

BY: J. B. [Signature]

Subscribed and sworn to before me this 22nd day of January, 1948.

Marion M. Hestert  
Notary Public

My commission expires June 4, 1951.

PLUGGING  
FILE SEC 26 T 18 R 15W  
BOOK PAGE 9 LINE 5