

15.009.20390.00.00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name L. K. Parrish

Complete Address 714 4th., Nat'l. Bldg., Wichita, Kansas

Lease Name Brown Well No. # 4

Location SW SW SE Sec. 32 Twp. 20 Rge. 12 (E) (W)W

County Barton Total Depth 3510

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor C. & G. Drilling Company

Address 1107 Union Nat'l. Bldg., Wichita, License No. <sup>Kansas</sup>

Operation Completed: Hour 11 A.M. Day 22 Month 7 Year 1969

The above well was plugged as follows:

8 5/8" 276' Cwc.

Circulated hole with heavy mud to 420', set plug, & displaced 45 sax cement thru  
drill pipe. Mud to 240' & displaced 25 sax cement thru drill pipe. Mud to 40',  
1/2 sax hulls, plug, & displaced 10 sax cement with Dowell Cementing Company's  
pump truck, cementing to base of cellar.

RECEIVED

STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

JUL 25 1969

INVOICED

CONSERVATION DIVISION  
Wichita, Kansas

Signed: [Signature]  
Well Plugging Supervisor

DATE 7/28/69

INV. NO. 162-w