

14
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 5 1963
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name C. E. Denman

Complete Address: 3115 Broadway, Great Bend, Kansas

Lease Name Hagen Well No. # 2

Location C S/2 NE NE Sec. 30 Twp. 20 Rge. 11 (E) (W)

County Barton Total Depth 3400

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 5:30PM Day 2 Month 12 Year 1963

The Above well was plugged as follows:

8 5/8" 248' Gwc.

Sanded hole back to 3380' & dumped 5 sx cement wh/dump bailer. Pulled
pipe. Set plug @:240'; dumped 2 sx Calseal on plug; let set 4 hrs. Bailed
hole dry; displaced 25 sx cement. Mud to 40'; set rock bridge; displaced
10 sx cement, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 12/5/62

INV. NO. 8232-w

Signed: [Signature]
Well Plugging Supervisor