
STATE OF KANSAS
STATE CORPORATION COMMISSION

15.009.01386.00.00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Barton County. Sec. 2 Twp. 18 Rge. 11 (E) (W)

Location as "NE/CNW¼SW¼" or footage from lines SE SE NE

Lease Owner Petroleum, Inc.

Lease Name Fox Well No. 1

Office Address 305 East Third, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 24, 1 19 1953

Application for plugging filed October 24, 1953

Application for plugging approved October 24, 1953

Plugging commenced October 24, 1953

Plugging completed October 24, 1953

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3355 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	253	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 150' and set wooden plug at 150'. Placed 1/2 sack hulls ahead of plug. Cemented and displaced 15 sacks cement through drill pipe onto plug and hulls at 150'. Mudded up to 40' and set second plug at 40'. Placed 1/2 sack hulls ahead of plug at 40'. Filled hole to bottom of well cellar with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1953
CONSERVATION DIVISION
Wichita, Kansas

10-30-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company

Address R.R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

W.W. Fisher (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W W Fisher

305 East Third, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 1953

Notary Public.

My commission expires October 13, 1954

24-7368-S 3-53-20M

PLUGGING
FILE SEC 2 T 18 R 11W
BOOK PAGE 132 LINE 26

15.009.01386.00.00

DRILLER'S LOG FOX #1

Petroleum, Inc., Operator

Garvey Drilling Company, Contractor

Drilling Commenced: October 11, 1953
Drilling Completed: October 21, 1953

Casing Record: 8 5/8" @ 253' w/150 sax

Section 2, Twp. 18S, Rge. 11W

Location: SE SE NE

County: Barton County, Kansas

Production: D & A

R.T.D.: 3355'

Figures below indicate bottom of formation:

145	Clay & Shale
175	Sand & Shale
320	Shale & Shells
400	Red Bed, Shale & Shells
612	Red Bed, Sand & Shells
625	Anhydrite
1200	Shale & Shells
1650	Lime & Shale
1690	Shale & Shells
2645	Lime & Shale
2785	Lime
2850	Lime & Shale
2895	Lime
3005	Lime & Shale
3260	Lime
3300	Lime & Conglomerate
3346	Conglomerate
3355	Lime
3355	R.T.D.

Tops:

Heebner:	2890 (-1088)
Brown Lime:	2994 (-1192)
Lansing:	3010 (-1208)
Conglomerate:	3297 (-1495)
Arbuckle:	3346 (-1544)

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W. W. Hinshaw

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1953
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 28th day of October, 1953.

PLUGGING
FILE SEC 2 T 18 R 11W
BOOK PAGE 132 LINE 26

Notary Public

My commission expires: October 13, 1954

15.009.01386.00.01

DRILLERS LOG

No. 1 Fox WASHDOWN

CASING RECORD:

(8-5/8" @ 253')-150 sks.

5-½" @ 3035.03'
w/75 sx cmt

TOTAL DEPTH: 3100'

COMPANY: Barnett Oil Co.

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: May 24, 1974

COMPLETED: May 28, 1974

DESCRIPTION:

SE SE NE
2-18S-11W
Barton County,
Kansas

ELEVATION: 1802 RB

FORMATION	FROM	TO	REMARKS
Drilling Cement	0	1475	
Washing Down	1475	3100	

RECEIVED
STATE CORPORATION COMMISSION
AUG 28 1974
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens
Linda H. Dickens

Subscribed and sworn to before me this 11th day of June, 1974.

D'Ann Drennan
Notary Public

My Commission Expires:

December 28, 1977

D'ANN DRENNAN
NOTARY PUBLIC
My Comm. Exp.
Dec. 28, 1977
SEDGWICK COUNTY, KANSAS