


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15.009.00178.00.00
WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barton County. Sec. 36 Twp. 17 Rge. 15 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE SE
Lease Owner Heathman & Company, Inc. & The Carl Todd Drilling Co.
Lease Name Bartonek Well No. #1
Office Address 254 N. Washington, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-29 1952
Application for plugging filed 11-28 1952
Application for plugging approved 11-28 1952
Plugging commenced 11-28 1952
Plugging completed 12-2- 1952
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3542' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
see Drillers Log						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rocked hole from 3561' to 3525' and ran 5
sacks of cement. Globe Cementing Company
pumped in 25 sacks of mud and 100 sacks
of cement to complete plugging.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Carl Todd Drilling Company
Address 404 KFH Building,
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Carl Todd (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl Todd

404 KFH Building, Wichita 2, Kansas
(Address)


SUBSCRIBED AND SWORN to before me this day of 19

My commission expires

Notary Public.

RECEIVED
CONSERVATION DIVISION
Wichita, Kansas

12-10-52



15.009.00178.00.00

THE CARL TODD DRILLING COMPANY
404 KFH Building,
Wichita 2, Kansas

The Carl Todd Drilling Company, et al
Bartonek No. 1
SE SE SE Sec. 36-17S-15W
Barton County, Kansas

Date Commenced: October 22, 1952
Date Completed: November 10, 1952

Rotary Tools: 0' to 3542'

Elevation: 1978' D. F. - 1980' R.B.

Casing Record:

10 3/4" casing cemented at 220'
with 130 sacks cement.
5 1/2" casing cemented at 3537'
with 100 sacks cement.

LOG

FORMATION TOPS - 0' to R.B.

0	40	Surface clay, shale
40	220	Shale, shells
220	485	Shale, shells, iron
485	510	Sand, shale
510	550	Red bed, shells
550	615	Sand, Red bed
615	850	Red bed, shells
850	1005	Red bed, shells
1005	1030	Anhydrite
1030	1220	Shale, shells
1220	1250	Shale, salt
1250	1525	Red bed, shale
1525	1710	Shale, shells
1710	1760	Lime, shale
1760	1880	Lime, shale
1880	2285	Lime, shale
2285	2490	Shale, lime
2490	3100	Lime, shale
3100	3355	Lime
3355	3391	Lime (cherty)
3391	3440	Lime
3440	3500	Lime, shale
3500	3537	Congl. chert.
3537	3542	Arbuckle - Total Depth

Lansing.....	3269
Congl.	3492
Arbuckle.	3535
Total Depth	3542

Drill Stem Test - 3536' to 3542'
Open 1 hour and 15 minutes. B.H.P.
weak blow for 1 hour. Recovered
90' gas 94' heavy oilcut mud.

I, Carl Todd do hereby certify that
the above log is correct to the best
of my knowledge and belief.

Carl Todd
Carl Todd

RECEIVED
CORPORATION COMMISSION
DEC 10 1952
REGISTRATION DIVISION
WICHITA, KANSAS

PLUGGING

FILE SEC 36 T 17 R 1524
BOOK PAGE 63 LINE 32