


15-009-01382-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 16 Twp. 17 Rge. 14 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines NE SE SW
Lease Owner Francis Oil & Gas, Inc.
Lease Name Roy Connor Well No. 1
Office Address Palace Building, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-21 19 53
Application for plugging filed 12-21 19 53
Application for plugging approved 12-21 19 53
Plugging commenced 12-21 19 53
Plugging completed 12-21 19 53
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3474 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	895'	-----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Top plug set at 40' with 10 sacks cement
Bottom plug set at 300' with 20 sacks cement

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Anschutz Drilling Company
Address 709 Union Nat'l Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. E. G. Koelling employee of contractor
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. G. Koelling
709 Union Nat'l Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of December, 1953

My commission expires May 2, 1956
Jacqueline Linn Notary Public

24-7368-S 3-53-20M

PLUGGING
FILE SEC 16 T 17 R 14W
BOOK PAGE 3 LINE 39

12-24-53

DRILLER'S LOG

Francis Oil & Gas, Inc.
 #1 Roy Connor
 NE SE SW - 16-17S-14W
 Barton County, Kansas

<u>FROM</u>	<u>TO</u>	
0	100	Surface clay & post rock
100	438	Shale & shells
438	510	Sand
510	585	Shale, shells & red rock
585	800	Red bed & shells
800	891	Red shale & shells
891	920	Anhydrite
920	1210	Red bed & pyrite
1210	1280	Red bed & shale
1280	1465	Salt
1465	1540	Shale
1540	1765	Shale & lime
1765	1825	Lime
1825	1845	Sandy lime & shale
1845	2065	Lime
2065	2215	Shale & lime
2215	2565	Shale
2565	2675	Shale & lime
2675	2815	Shale
2815	2910	Shale & lime
2910	3100	Lime
3100	3110	Blue sticky shale
3110	3175	Lime, red rock & shale
3175	3350	Lime
3350	3405	Lime & shale
3405	3430	Conglomerate
3430	3443	Conglomerate & Arbuckle lime
3443	3463	Lime, shale & chert
3463	3474	Lime
3474		ROTARY TOTAL DEPTH

COMMENCED: 12-8-53
 COMPLETED: 12-21-53

CASING RECORD

Set 8-5/8" surface casing at 895'
 with 400 sacks cement.

TOPS (RB)

Anhydrite 891
 Toronto 3100
 Heebner 3085
 Brown Lime 3151
 Lansing 3162 (-1238)
 B/KC 3367
 Conglomerate 3376
 Re-worked Arbuckle 3436
 Solid Arbuckle 3447

DRILL STEM TEST'S

3154-3185, open 1 hour, recovered
 30' muddy water, BHP 175#, closed
 15".
 3365-3430, open 1 hour, recovered
 15' mud, BHP 60#, closed 15".
 3438-3443, open 1 hour, recovered
 6' mud, BHP 1100#, closed 15".

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of
 the log of the #1 Roy Connor located NE SE SW Section 16-17S-14W, Barton County,
 Kansas.

ANSCHUTZ DRILLING COMPANY

BY: *E. G. Koelling*
 E. G. Koelling

Subscribed and sworn to before me this 23rd day of December, 1953.

Jaqueline Herman
 Notary Public

My Commission Expires: May 2, 1956.

