

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Blifling Building
Wichita, Kansas

15.009.00990.00.00
WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH

X	.		

Locate well correctly on above
Section Plat

Barton County. Sec. 9 Twp. 20 Rge. 13 (E) W (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. Center W line NW NW
Lease Owner R. F. FINE DRILLING COMPANY
Lease Name Hart Well No. 1
Office Address Cork Building, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date, well completed May 9 19.41
Application for plugging filed May 13 19.41
Application for plugging approved May 13 19.41
Plugging Commenced May 13 19.41
Plugging Completed May 14 19.41
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well G. T. Alexander
Producing formation None Depth to top Bottom Total Depth of Well 3524 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand	Water	25	85	8 5/8	351	None
Sand	Water	250	317			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Heavy mud pumped through drill pipe at 2700 feet.
Heavy mud pumped through drill pipe at 2200 feet.
Heavy mud pumped through drill pipe at 1700 feet.
Heavy mud pumped through drill pipe at 1200 feet.
Heavy mud pumped through drill pipe at 700 feet.

Permanent bridge placed at 351 feet and cemented through drill pipe from 351 feet to 336 feet.

Filled with heavy rotary mud from 336 feet to 14 feet.

Plug at 14 feet and cement from 14 feet to 8 feet.

Mud to surface. Surface pipe cut off and steel plate welded tight over top of surface casing.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to R. F. FINE DRILLING COMPANY
Address Box 760, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
C. H. TODD (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. H. Todd

Box 760, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 15 day of May, 1944

My commission expires April 16, 1944

Samuel H. Yeo Notary Public.



5-16-41

LOG

Hart Well Number 1
 660' from N line and 330' from W line, NW $\frac{1}{4}$
 Section 9-20S-13W
 Barton County, Kansas

Commenced April 28, 1941
 Completed May 14, 1941

R. W. RINE DRILLING COMPANY

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	
SAND AND CLAY	0	295	
SHALE AND SHELLS	295	351	8 5/8 casing cemented at 351'.
RED BED	351	390	
RED AND BLUE SHALE	390	725	
ANHYDRITE	725	760	
RED AND BLUE SHALE	760	920	
SHALE AND SHELLS	920	1238	
SALT	1238	1450	
SHALE AND SHELLS	1450	1570	
LIME AND SHALE	1570	1750	
SHALE AND SHELLS	1750	2080	
SHALE AND LIME	2080	2362	
SHALE	2362	2485	
SHALE AND LIME	2485	2620	
SHALE AND SHELLS	2620	2720	
SHALE	2720	2785	
LIME	2785	2803	
LIME AND SHALE	2803	2835	
LIME	2835	2915	
LIME AND SHALE	2915	2980	
LIME	2980	3125	
SHALE AND LIME	3125	3208	
LIME AND SHALE	3208	3257	
SHALE AND LIME	3257	3304	
LIME	3304	3452	
SHALE LIME & CONG	3452	3494	
LIME	3494	3524	Total Depth Dry and Abandoned.

FILE 9 20 13W
 BOOK 137 LINE 33

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

I, C. H. Todd, Vice-President of the R. W. Rine Drilling Company, do hereby certify, the above to be a true and correct copy of the log of the Hart Well Number 1, located in the Center of the West Line of NW $\frac{1}{4}$ of NE $\frac{1}{4}$ of Section 9, Township 20 S, Range 15 W, Barton County, Kansas.

C. H. Todd

Sworn and subscribed to before me this 15th day of May 1941, at Great Bend, Kansas.

Samuel N. Yeo
Notary Public

My Commission Expires: April 16 1944.

FILE BOOK 9 20 R 15W 137 LINE 33