


15.009.00385.00.00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Form to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 9 Twp. 20S Rge. 12 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE $\frac{1}{4}$ NE $\frac{1}{4}$ NE $\frac{1}{4}$
Lease Owner National Associated Petroleum Company
Lease Name Rosa Dahm Well No. 1
Office Address Fifth Floor Ritz Bldg. - Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Nov. 10, 1951
Application for plugging filed Nov. 10, 1951
Application for plugging approved Nov. 10, 1951
Plugging commenced Nov. 10, 1951
Plugging completed Nov. 10, 1951
Reason for abandonment of well or producing formation Dry Hole
(Not commercially productive)
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3502 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Kansas City	Oil & Water	3114	3366			
Arbuckle	Water	3419	3502			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Set Halliburton plug at 208'. Pumped in 20 sacks cement. Filled to top with mud. Set second plug at 35'; filled to top with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 10 1951
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Honaker Drilling Company, Inc.
Address McBride Building, Great Bend, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
C. Edwin Mohler (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. Edwin Mohler, Chief Geologist
5th Floor Ritz Bldg. - Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of November, 1951

Mafine M. Davis
Notary Public.

My commission expires February 19, 1953

FILED
9-20-51
154-9

DRILLERS LOG

COMPANY: National Associated Petroleum Co. Sec: 9 T. 20S R. 12W
Loc: NE 1/4 NE Barton County, Kansas

FARM: Rosa Dahm NO: 1

TOTAL DEPTH: 3502
Comm: 10-22-51 Comp: 11-10-51
CONTRACTOR: Honaker Drilling Co., Inc.

Casing: 6 5/8 200'

95	Sand	
103	Iron	
203	Clay	Cemented 3 5/8" at 200' with
260	Shale - Clay	200 sacks cement and 200# C.C.
560	Shale Shells, Red Bed	
590	Shale - Lime	
1150	Sand - Lime - Shale	
1425	Shale and Shells	
1565	Lime	
1675	Lime	
1860	Lime	
2025	Shale - Lime	
2210	Lime - Shale	
2320	Shale and Shells	
2590	Shale and Lime	
2740	Lime and Shale	
2810	Lime	
2990	Lime	
3075	Shale and Lime	
3155	Lime and Shale	
3190	Lime	
3203	Lime and Shale	
3230	Lime	
3290	Lime and Shale	
3365	Lime and Shale	
3395	Shale and Lime	
3405	Lime	
3408	Lime and Chat	
3502	Lime T.D.	

I CERTIFY THAT THIS IS THE TRUE AND CORRECT COPY OF THE ABOVE LOG, TO THE BEST OF MY KNOWLEDGE.

Joe J. Honaker

Subscribed and sworn to before me this 13 day of November 19 51

Kenneth L. Fisher
Notary Public

My Commission Expires 6-25-55

REC 20 1951

OK