


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County. Sec. 36 Twp. 20 Rge. (E) 11 (W)  
Location as "NE/CNW/SW" or footage from lines C S/2 NW SE  
Lease Owner Petroleum, Inc.  
Lease Name ISERN-BEAVER 'A' Well No. 2  
Office Address 311 East Third, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 9 19 55  
Application for plugging filed August 9 19 55  
Application for plugging approved August 9 19 55  
Plugging commenced August 9 19 55  
Plugging completed August 9 19 55  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well MR. W. H. HORNER, GREAT BEND, KANSAS  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3390 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	325'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded up to 300' and placed first plug with  
20 sacks cement on top of plug. Mudded up to 35' and  
placed second wooden plug at 35'. Displaced 10 sacks  
cement top of plug to base of well cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company  
Address R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Karl E. Becker (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Karl E. Becker  
311 East Third, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of August, 1955

My commission expires August 8, 1959  
Oliver Morrison Notary Public.

**PLUGGING**  
MLK SEC. 36 T. 20 R. 11W  
BOOK PAGE 142 LINE 22

RECEIVED  
SEP-2 1955  
CONSERVATION DIVISION  
Wichita, Kansas  
9-2-55

# WELL LOG

15.009.00553.00.00

COMPANY **Petroleum, Inc.**

SEC. 36 T. 20S R. 11W

FARM **ISERN-BEAVER 'A'** NO. 2

LOC. **C S/2 NW SE**

**1980' FEL**

**1650' FSL**


TOTAL DEPTH **3390'**

COUNTY **Barton**

COMM. **August 1, 1955**

COMP. **August 9, 1955**

CONTRACTOR **Garvey Drilling Company**



CASING **8-5/8" @ 325' w/250 S&X**

ELEVATION **1766' DF**  
**1768' RB**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

125	Sand
325	Shale & Shells
475	Anhydrite
1350	Shale & Shells
1440	Shale & Lime Streaks
1815	Lime
1950	Lime & Shale
2005	Lime
2225	Shale
2695	Shale & Lime
2915	Lime
2965	Shale & Lime
3280	Lime
3325	Cherty Lime
3350	Lime
3370	Simpson Sand
3390	Arbuckle

### Sample Tops

Heebner:	2897 (-1129)
Toronto:	2913 (-1145)
Douglas:	2929 (-1161)
Brown Lime:	3028 (-1260)
Lansing:	3050 (-1282)
Conglomerate:	3297 (-1529)
Arbuckle:	3368 (-1600)

R.T.D. 3390'

State of KANSAS }  
County of SEDGWICK } ss:

RECEIVED  
COMMISSION  
1955  
DIVISION  
Kansas

**PLUGGING**  
SEC 36 T 20 R 11W  
PAGE 142 LINE 22

I, Karl E. Becker of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the ISERN-BEAVER 'A' #2 well

Subscribed and sworn to before me this 16th day of August 19 55

My Commission Expires: August 8, 1959

Karl E. Becker  
Alvin Morrison  
NOTARY PUBLIC