

15-009-07261-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 24 1967  
07-24-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. C. R. Moore of N. C. R. A. has this

date requested permission to plug the following described well:

Mr. Ralph Booker guarantees payment of the plugging fee.

Operator's full Name: N. C. R. A.

Complete Address: Box 6, Great Bend, Kansas 67530

Lease Name: Ehly Well No. # 5

Location: SW NE SW Sec. 15 Twp. 16 Rge. 12 (E)(W) W

County Barton Total Depth 3351 Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Ben Thompson was instructed to plug the well as follows:

8 5/8" 520' Cwc.

Set bottom plug @ 3050' & dumped 5 sax cement with dump bailer. Pulled

pipe. Mud to 350', set 10' rock bridge, & displaced 25 sax cement.

Mud to 40', set rock bridge, & displaced 10 sax cement, cementing to

base of cellar.

Very truly yours,

Don Luman  
Conservation Division Agent