



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

April 24, 1963 RECEIVED  
 STATE CORPORATION COMMISSION

APR 30 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Sherrill Compton of E. H. Adair Oil Company has this  
 date requested permission to plug the following described well:

Mr. Compton guarantees payment of the plugging fee.

Operator's full Name: E. H. Adair Oil Company

Complete Address: 1005 E. Second, Wichita, Kansas

Lease Name: Fair "D" Well No. 1

Location: NE NE SE Sec. 10 Twp. 21 Rge. 9  (E)  (W)  (S)  (N)

County Rice Total Depth 3391' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Compton was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 220'. Push  
plug and 1/4 sack hulls to 220' and cement with 20 sacks  
through drill pipe. Fill hole with mud to 35'. Push  
plug and 1/4 sack hulls to 35' and cap hole with 10 sacks  
cement. Bridge, and cement rathole with 2 sacks.

Very truly yours,

*William J. Lawrence*  
 Conservation Division Agent