



15.159.30220.0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

January 6, 1966

RECEIVED
STATE CORPORATION COMMISSION

JAN 10 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Clarence Micheals of Sage Drilling Co. has this

date requested permission to plug the following described well:

Mr. Micheals guarantees payment of the plugging fee.

Operator's full Name: C & S Well Servicing Company

Complete Address: Lyons, Kansas

Lease Name: Waknitz Well No. 1

Location: NW NE SE Sec. 9 Twp. 21 Rge. 9 (E) (W) X

County Rice Total Depth 3540' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Micheals was instructed to plug the well as follows:

Pump 140 sacks cement through drill pipe at 3540'. Fill

hole with mud to 250'. Push plug and 1/2 sack hulls to 250'

and cement hole with 40 sacks. Fill hole with mud to 40'

Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks

cement. Bridge rathole, and cement with 5 sacks.

(Cities Service underground storage area.)

Very truly yours,

Arthur J. Loman
Conservation Division Agent