



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

April 15, 1963

RECEIVED
 STATE CORPORATION COMMISSION

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

APR 22 1963
 4-22-63

Dear Sir:

Mr. Kenneth Johnson of E. H. Adair Oil Co. has this

date requested permission to plug the following described well:

Mr. Johnson guarantees payment of the plugging fee.

Operator's full Name: E. H. Adair Oil Company

Complete Address: 1005 E. Second, Wichita, Kansas

Lease Name: McFarland "B" Well No. 1

Location: C NW NE Sec. 26 Twp. 21 Rge. 8 (D) (W) X

County Rice Total Depth 3367' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Johnson was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 270'. Push
plug and $\frac{1}{4}$ sack hulls to 270' and cement with 20 sacks
through drill pipe. Fill hole with mud to 35'. Push
plug and $\frac{1}{4}$ sack hulls to 35' and cement with 10 sacks.
Bridge, and cement rathole with 2 sacks.

Very truly yours,

[Signature]
 Conservation Division Agent