



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 22 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Cameron of H-30 Drilling, Inc. has this date requested permission to plug the following described well:

Mr. R. D. Olson guarantees payment of the plugging fee.

Operator's full Name: R. D. Olson

Complete Address: 353 N. Armer, Wichita, Kansas

Lease Name: Schartz Well No. # 1

Location: SE SE SW Sec. 36 Twp. 20 Rge. 13 (E) (W) W

County: Barton Total Depth 3545 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fred Cameron was instructed to plug the well as follows:

8 5/8" csg. 205' Cwc.

Circulated hole with heavy mud to 480', set plug, & displaced 40 sax

cement thru drill pipe. Mud to 200' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Allied Cementing Company's pump truck, cementing to

base of cellar.

Very truly yours,

D. L. ...
Conservation Division Agent