



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY O. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 1/2 Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

MAY 17 1965

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. O. C. Arnott of Bergman Drlg. Inc. has this date requested permission to plug the following described well:

Mr. Harold Bergman guarantees payment of the plugging fee.

Operator's full Name: Bergman Oil Company

Complete Address: 425 Union CenterrBldg., Wichita, Kansas

Lease Name: Welsh Well No. # 2

Location: NW NE NW Sec. 30 Twp. 20 Rge. 12 (E) (W) W

County Barton Total Depth 3541 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. O. C. Arnott was instructed to plug the well as follows:

8 5/8" 341' Cwc.

Circulated hole with heavy mud to 340'; set plug with 1/4 sax hulls; displaced 25 sax cement thru drill pipe.

Mud to 40'; 1/2 sax hulls; plug & displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Law Truman  
Conservation Division Agent