



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Charles L. Carlock of Charles L. Carlock has this date requested permission to plug the following described well:

Mr. Charles L. Carlock guarantees payment of the plugging fee.

Operator's full Name: Charles L. Carlock

Complete Address: 1515 Hillcrest, Newton, Kansas 67114

Lease Name: Nordman Well No. # 1

Location: SE NW NE Sec. 4 Twp. 19 Rge. 15 (E)(W) W

County: Barton Total Depth 3310 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Johnnie Jones was instructed to plug the well as follows:

8 5/8" 920' Cwc.

Sanded hole back to 3260' & dumped 5 sax cement with dump bailer.

Pulled pipe. Mud to 380', set 30' rock bridge, & displaced 30 sax

cement. Mud to 40', set rock bridge, & displaced 10 sax cement,

cementing to base of cellar.

Very truly yours,

Don Johnson
Conservation Division Agent