

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE-NE-NE

SEC. 3 TWP. 18 RGE. 14-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1-B Lease Everleick

Operator Murphy Oil Co. Address #1604 Philtower, Tulsa-Okla.

Field _____ County Barton

Total Depth 3398 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 850 ft. Circulated with cement
4 1/2 casing set at 3383 ft - 150 sacks of cement. Plugged
back to 3375 ft. with sand. Mixed 3 sacks of cement
at 3375 ft. Shot off & pulled the 4 1/2 casing - mud
& 250 ft. Set rock bridge & 20 sacks of cement
at 250 ft. mud to 35 ft. Plug & 10 sacks of cement
at the surface.

PLUGGING
FILE SEC 3 T 18 R 14-W
BOOK PAGE 84 LINE 34

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1953
CONSERVATION DIVISION
Wichita, Kansas

O. H. Stouck
District Conservation Agent
Date 12-12-53