

15.009.20340.00.00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 1 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name O. A. Sutton

Complete Address 800 Sutton Place Wichita, Kansas 67202

Lease Name Schumacher Well No. 1

Location App. SE SW NW Sec. 30 Twp. 20 Rge. (E) (W) 13

County Barton Total Depth 3563'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Ralph Comstock

Address Stafford, Kansas License No. 490

Operation Completed: Hour 4:30P Day 30 Month 7 Year 1969

The above well was plugged as follows:

Total Depth 3563' 8 5/8 csg set at 181' cwc 225 sk.

5 1/2 csg set at 3561' cw 100 sk cmt. with top perf. (3528)

Filled 5 1/2 csg W/sd (3510-3563) Dumped 4 sk cmt W/dump bailer. (3475-3510)

Cutoff and recovered 2220' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk

50-50 poz cmt W/6% total gel. Max. pres. 500 lbs. SI pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/1/69

INV. NO. 212-4

Signed: Leo J. Messer
Well Plugging Supervisor