

15.009.06248.00.01

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

f

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name B & R Oil Co.

Complete Address Box 253 Great Bend, Kansas 67530

Lease Name Rusco Well No. 1

Location NW NW NE Sec. 17 Twp. 19 Rge. 12 CEX (W) X

County Barton Total Depth 3477' 3478'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698 Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 12:30 PM Day 19 Month 12 Year 1978

The above well was plugged as follows:

Sanded back to 3290' and 4 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 3 sx hulls

15 sx mud gel, plug, and 100 sx cement.

Max pres. 1000#. Shut in pres. 400#.

Recovered 1700' of 4 1/2" casing.

Plugged back to 3290'. Top perforation at 3317'.

3477' of 4 1/2" casing cemented with 150 sx cement.

236' of 8 5/8" surface casing cement circ.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 22 1978  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Donald Rankin  
Well Plugging Supervisor

DATE 12-28-78  
INV. NO. 8813-W