

15-009-15771-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barton County, Sec. 14 Twp. 16 Rge. 12 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C N/2 SW SE
Lease Owner Morgenstern & Specter, Inc.
Lease Name Weber Well No. 5
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 3-23-62 19____
Plugging completed 3-29-62 19____
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3358 Feet
Slow depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	245'	None
				5-1/2"	3341'	2906'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3358', sanded to 3320' and dumped 5 sacks of cement @ 3320' with dump bailer. Pulled 5 1/2" to 400' and pumped in 10 sacks of jall mud, pulled pipe to 350' and pumped in 20 sacks of cement. Pulled pipe to 220' and pumped in 20 sacks of cement. Pulled balance of 5 1/2" casing, bailed fluid to 30' and ran 10 sacks of cement to base of cellar.

4-10-62

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

APR 11 1962

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or XXXXXXXXXXXX (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of April, 1962

My commission expires May 20, 1964

Milton J. Volin
Notary Public.


15-009-15771-00-00
 WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk. Bldg., Wichita, Kansas

Company. BLACK-MARSHALL OIL CO.
 Farm. Mary Weber No. 5.

SEC. 14 T. 16 R. 12 W.
 CN $\frac{1}{2}$ SW SE

Total Depth. 3358'
 Comm. 6-18-44 Comp. 7-1-44
 Shot or Treated.
 Contractor. Ferrell-Young Drilling Co.
 Issued. 8-26-44

County. Barton
 KANSAS



CASING:
 8 5/8" 245' Cem.
 5 1/2" 3341' Cem.

Elevation. _____

Production. Pot. 206 B.
 No wtr

Figures Indicate Bottom of Formations.

cellar	4
shale	75
shale & shells	225
sand	239
shale blue	242
shale & shells	795
anhydrite	825
shale & shells	1230
salt	1420
shale & shells	1745
lime & shell bks	1995
lime	2020
lime & shell bks	2230
lime & shale	2245
shale & shells	2670
lime	3000
shale & shells	3073
lime	3343
sand	3346
Rotary Total Depth	
lime	3358
Total Depth.	

Sample Tops: (Rotary Total Measurements)

Topeka	2670
Hessner shale	2980
Dodge	2996
Base Oread	3000
Lansing White	3089
Base K.C.	3333
Gorham Sand	3341
Arbuckle	3355