


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rice County, Sec 21 Twp. 21S Rge. (E) 9 (W)
Location as "NE/CNW/SE/SW" or footage from lines Approx. C NE NE NW
Lease Owner Keener Oil Company
Lease Name Pearl Royalty Well No. 1
Office Address 406 Nat'l Bank of Tulsa Bldg., Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 28 1968
Application for plugging filed Verbal Approval 19
Application for plugging approved Verbal Approval 19
Plugging commenced August 28 1968
Plugging completed August 28 1968
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	252'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 3,546 feet (rotary total depth) to 3,425 feet. Set bottom plug at 3,425 feet and cemented with 160 sacks cement to 2,800 feet. Filled hole with heavy rotary mud to 500 feet. Set plug at 500 feet and cemented with 25 sacks cement. Filled hole with heavy rotary mud to 225 feet. Set plug at 225 feet and cemented with 25 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented with 10 sacks cement, 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
SEP 6 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, INC.
Address 200 N. Main St., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer
200 N. Main St., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of September, 1968

My commission expires April 21, 1971

Martha Hartpence
Martha Hartpence Notary Public.

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15-159-20146-0000

COMPANY Keener Oil Company

SEC. 21 T. 21S R. 9W
 LOC. App. C NE NE SW


FARM Pearl Royalty No. 1

TOTAL DEPTH 3,546'
 COMM. August 19, 1968
 SHOT OR TREATED
 CONTRACTOR H-30, INC.
 ISSUED

COMP. August 28, 1968

COUNTY Rice

KANSAS



CASING

20	10		
15	8	-5/8" 252' cemented w/225 sx cement	ELEVATION 1680 KB
12	6		
13	5		

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS - all measurements from K.B.

Surface Soil, Shale & Shells	253
Shale & Shells	765
Shale	1130
Lime & Shale	1754
Shale & Lime	2090
Lime & Shale	2410
Lime	2550
Lime & Shale	2680
Lime	3477
Lime & Shale	3542
Lime	3546
Rotary Total Depth	3546

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 6 1968
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer
 Arlo B. Romer

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 5th day of September, 1968.

Martha Hartpence
 Martha Hartpence Notary Public

My Commission Expires:

April 21, 1971