

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-22,161-0000

LEASE NAME Snider "B"

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-9

3135 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 9 TWP. 21 RGE. 10 (X) or (W)

COUNTY Rice

Date Well Completed 11-20-86

Plugging Commenced 11-20-86

Plugging Completed 11-21-86

LEASE OPERATOR Galloway Petroleum Exploration, Inc.

ADDRESS 300 Broadway Plaza Bldg. Wichita, KS 67202

PHONE# (316) 267-8355 OPERATORS LICENSE NO. 4661

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Salina, Ks.

Is ACO-1 filed? operator to be filed by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @ 3375' w/30 sacks cement thru drill pipe

Next Plug: @ 400' w/50 sacks " " " "

Top Plug: @ 60' w/20 sacks " " " "
10 sacks in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (Employee of Operator) or ~~(Operator)~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Leonard Williamson

(Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 26 day of November, 19 86

Dorothy M Hague
Notary Public

My Commission Expires: 5-5-90



11-26-83

Form CP-4
Revised 08-84

NOV 26 1986

DRILLER'S WELL LOG

DATE COMMENCED: November 14, 1986
DATE COMPLETED: November 20, 1986

Galloway Petroleum Exploration
SNIDER "B" #1-9
165' S of W/2 SE NW
Rice County, Ks.

ELEVATION: 1726 K.B.

0 - 389'	Surface Soil, Sand, Shale, Red Bed
389 - 407'	Anhydrite
407 - 2478'	Lime & Shale
2478 - 2537'	Lime
2537 - 2582'	Shale & Sand
2582 - 2874'	Lime
2874 - 2920'	Shale & Lime
2920 - 3006'	Shale
3006 - 3028'	Lime & Shale
3028 - 3272'	Lime
3272 - 3404'	Shale, Lime, Sand
3404 - 3450'	Dolomite
3450'	RTD

FORMATION DATA

Anhydrite	389'
Howard	2478'
Severy	2537'
Topeka	2582'
Heebner	2874'
Toronto	2890'
Douglas	2920'
Br. Lime	3006'
Kansas City	3028'
Base K.C.	3272'
Simpson	3322'
Arbuckle	3404'
RTD	3450'

Surface Pipe: Set new
8-5/8", 20 # pipe @208'
w/180 sacks 60/40 pozmix
2% gel 3% cc.


A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 26 day of November 1986.



Dorothy M. Hague
Notary Public