


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Flat

Rice County, Sec. 7 Twp. 21S Rge. 10 (W) (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW/4 NW/4 SW/4  
Lease Owner The El Dorado Refining Company  
Lease Name (Bert) Miller Well No. 1  
Office Address 407 Brown Building  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 11-3-1951  
Application for plugging filed 11-3-1951  
Application for plugging approved 11-3-1951  
Plugging commenced 11-3-1951  
Plugging completed 11-3-1951  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19...  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Ruel E. Durkee  
Producing formation Depth to top Bottom Total Depth of Well 3440 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	280'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from...feet to...feet for each plug set.

Filled hole with heavy mud.  
Set bottom plug at 280'. Cemented with 15 sacks through drill pipe. Filled hole with heavy mud. Set top plug at 35'. Cemented with 10 sacks.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Group Exploration Company  
Address Box 218  
Sterling, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.  
Rollin Mead (employee of owner) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Rollin Mead  
Sterling, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of November, 1951.

My commission expires 9-17-53 Notary Public.

PLUGGING  
FILE SEC 71 X 2102  
DATE FILED 11-15-51

GROUP EXPLORATION CO.

BOX 218  
STERLING, KANSAS

WELL LOG ----- (BERT) MILLER #1

Location - NW/4 NW/4 SW/4 of Section 7-21S-10W, Rice County, Kansas

Owner - The El Dorado Refining Company  
Contractor - Group Exploration Company

Commenced - 10-21-51  
Completed - 11-3-51

Total Depth - 3440'

LOG

0- 70	Sand
70- 160	Shale and Red Bed
160- 425	Red Bed
425- 460	Anhydrite
460-1200	Shale and Shells
1200-2520	Shale and Lime
2520-2590	Shale
2590-2905	Lime
2905-2960	Lime and Shale
2960-3020	Shale
3020-3275	Lime
3275-3315	Lime and Shale
3315-3338	Conglomerate
3338-3365	Simpson Sand
3365-3385	Sand
3385-3430	Lime
3430-3440	Arbuckle Lime

CASING RECORD

280' of 8-5/8" Surface Pipe  
Cemented with 200 Sacks Bulk Cement  
(1' off bottom)

PLUGGING  
FILE SEC-7-T-2-R10W  
PAGE 12 LINE 15

RECEIVED  
STATE COMMISSION  
NOV - 8 1951  
OIL AND GAS DIVISION  
Wichita, Kansas