

130 S. Market, Room 2078
Wichita, Kansas 67211

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

2260 Ft. from North Line of Section
990 Ft. from West Line of Section

LEASE OPERATOR F.G. Holl Company, L.L.C. SPOT LOCATION 50' N of SE SW NW
ADDRESS P.O. Box 780167 Section 7 Township 21s Range 10w
CITY, STATE, ZIP Wichita, Kansas 67278-0167 County Rice
PHONE # 316-684-8481 Date Well Completed June 5, 2001
Character of Well Dry and Abandoned Date Plugging Commenced June 5, 2001
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed June 5, 2001

The plugging proposal was approved on June 5, 2001 at 8:52 am (date)
by Doug Lewis (KCC District Agent's Name)
Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 3450

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		CASING RECORD					
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT	
Surface Soil and Sands	Water sands	0	110				
Redbeds	Shale	110'	225'	8-5/8"	213.77	0'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Received plugging orders from Doug Louis at 11:55 am on 6/4/01. Plugging began at 4:00 am on 6/5/01.
Plugged using 180sx of 60/40 Poz, 4% Gel. Heavy mud in hole from 3450' to 3360', then 25sx, heavy mud to 1250', then 35sx, heavy mud to 900', then 35sx, heavy mud to 275', then 35sx, heavy mud to 60', then 25sx cement to surface. Plug down at 7:45 am on 6/5/01 by Acid Services, ticket #03585. Plugged mousehole 10sx, rathole 15sx.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company, L.L.C. (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M. Talbott
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 6th day of June, 2001



Pamela S. Fields
(Notary Public)

My Commission Expires:

JUN 7 2001

OR

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

Frederick "A" 1-7

LOCATION: 50' N of SE SW NW
API: 15-159-22388-0000

Section 7 T 21s R 10w
Rice County, Kansas

OWNER: F.G. Holl Company, L.L.C.
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 25-May-01
COMPLETED: 05-Jun-01

TOTAL DEPTH: DRILLER 3450 FEET
LOGGER 3445 FEET

Ground Elevation: 1728
KB Elevation: 1737

LOG

0 -	2 FEET	Top Soil
2 -	17 FEET	Clay
17 -	26 FEET	Sand and Gravel
26 -	29 FEET	Clay
29 -	40 FEET	Fine Sand
40 -	110 FEET	Sand and Gravel
110 -	440 FEET	Redbeds
440 -	475 FEET	Anhydrite (Driller's)
475 -	1286 FEET	Redbeds, Shales and Salt
1286 -	3386 FEET	Limestone, Shale and Dolomite
3386 -	3450 FEET	Arbuckle

CASING RECORDS

Surface Casing-8-5/8"

Spud @ 8:00 am on 5/25/01. Drilled 12-1/4" hole to 225'. Ran 5 joints of new 23# 8-5/8" surface casing, tally 213.77' set at 224' KB. Cemented with 225 sx 60/40 Poz, 2% Gel and 3% CC, Cement in cellar. Plug down at 11:15 am on 5/25/01 by Acid Services. Ticket #03670.

Plugging Record

Received plugging orders from Doug Louis at 11:55 am on 6/4/01. Plugging began at 4:00 am on 6/5/01. Plugged using 180sx of 60/40 Poz, 4% Gel. Heavy mud in hole from 3450' to 3360', then 25sx, heavy mud to 1250', then 35sx, heavy mud to 900', then 35sx, heavy mud to 275', then 35sx, heavy mud to 60', then 25sx cement to surface. Plug down at 7:45 am on 6/5/01 by Acid Services, ticket #03585. Plugged mousehole with 10sx and rathole with 15 sx.

DEVIATION SURVEYS

1/2 degree(s) at	225	feet
1 degree(s) at	2598	feet
3/4 degree(s) at	3301	feet
1 degree(s) at	3450	feet

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 7 2001

CONSERVATION DIVISION