

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Aspen Resources, Ltd.

Complete Address 710 One-Twenty Bldg., Wichita, Kansas 67202

Lease Name Coyne Well No. 1

Location C NW NW Sec. 13 Twp. 21 Rge. 8 (E) (W)

County Rice Total Depth 3377'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pawnee Drilling Company

Address Box 783, Great Bend, Kansas License No. 633

Operation Completed: Hour 10 AM Day 22 Month January Year 1971

The above well was plugged as follows:


Hole filled with sand to 3350' and cemented with 5 sacks cement!

Rock bridge set from 210' to 200' and 25 sacks cement dumped on bridge with dump
bailer. Hole bailed dry and cemented with 10 sacks cement (total 35 sacks).

Hole filled with mud to 40'. Rock bridge set from 40' to 30' and hole cemented to
base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 1/28/71
INV. NO. 3259-W

Signed: 
Well Plugging Supervisor