

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE-NE-NW

SEC. 14 TWP. 16 RGE. 12-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Thaires

Operator B & R. Willing, Inc. Address Box #232 - Russell - Kans.

Field _____ County Barton

Total Depth 3388 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 255 ft. Circulated with cement
5 1/2" casing at 3359 ft. Cemented with 100 sacks cement.
Plugged back to 3095 ft. with Trench Wells Plug
& shot - dumped 4 sacks of cement at 3095 ft.
Shot off & pulled the 5 1/2" casing - Mud to 255 ft.
Set Rock Bridge & 15 sacks of cement at 255 ft.
Mud to 30 ft. Plug & 10 sacks of cement
at the surface.

RECEIVED
STATE CORPORATION COMMISSION

JAN 20 1951

CONSERVATION DIVISION
Wichita, Kansas

C. R. Street
District Conservation Agent

Date 1-17-51

PLUGGING
FILE SEC 14 T 16 R 12W
BOOK PAGE 56 LINE 39