


15-009-15772-00-00

DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 4-22

LOCATION SW-SW-SE

SEC. 14 TWP. 16 RGE. 12W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 6 Lease M. Weber "West"

Operator Kath Cook, Refinery, Assn Address 820 N. B. Bldg. Wichita-Kans.

Field _____ County Barton

Total Depth 3382 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 5/8 - 232 ft. Circulated with cement:
5% casing set at 3351 ft. Plugged back to 3340 ft
with chat. Dumped 6 sacks of cement at 3340 ft.
Shot off & pulled the 5% casing - filled with mud
& 232 ft. Back Bridge & 15 sacks of cement at 232 ft
Mud to 30 ft - Bridge & 10 sacks of
cement at the surface
West Supply - Plugging - Cont'd

RECEIVED
Conservation Div.
MAY 26 1950

STATE CORPORATION
COMMISSION

C. H. Stone
District Conservation Agent

Date 5-24-50

PLUGGING
FILE SEC. 14 T. 16 R. 12W
BOOK PAGE 4 LINE 24