

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

RECEIVED
 STATE CORPORATION COMMISSION

MAR 27 1963

CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Morton Specter of Morgenstern & Specter has this date requested permission to plug the following described well:

Mr. Morton Specter guarantees payment of the plugging fee.

Operator's full Name: Morgenstern & Specter, Inc.

Complete Address: Box 661, Russell, Kansas

Lease Name: Weber Well No. # 2

Location: CSL NE SE Sec. 14 Twp. 16 Rge. 12 (E) (W)

County Barton Total Depth 3364 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Lynch was instructed to plug the well as follows:

No surface pipe. Old cable hole.

Sanded hole back to 3340' & dumped 4 sax cement with
dump bailer. Pulled pipe. Run 2" tubing to 320'; circulated
hole with mud. Pulled one joint tubing; displaced 50 sax
cement thru tubing @ 300' with pump truck. Pulled re-
maining tubing; set rock bridge @ 30' & 25 sax cement,
cementing to base of cellar.

Law Truman
 Conservation Division Agent