



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

March 18, 1971

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 22 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Cameron of H-30 Drilling, Inc. has this

date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.Operator's full Name: Keener Oil CompanyComplete Address: 406 Nat'l Bank of Tulsa Bldg., Tulsa, Oklahoma 74103Lease Name: Parkington Well No. 1Location: SE NE NW Sec. 21 Twp. 21 Rge. 9 (E) (W) XCounty: Rice Total Depth 3538' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Cameron was instructed to plug the well as follows:

Pump 140 sacks cement through drill pipe from 3420' to 2934'. (requested by Cities Service Gas Co. to protect underground natural gas storage area.)

Pump 25 sacks cement through drill pipe at 250'. Push plug and $\frac{1}{2}$ sack hulls to 40' and cap hole with 10 sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

William J. Leonard
Conservation Division Agent